BRUHAT BANGALORE MAHANAGARA PALIKE

3BMP/2014-15/OW/WORK_INDENT16721/CALL-

APPROVED SCHEDULE - B

EE/BTP/BMP/E-PMT/10/2014-15, Date: 21.02.2015

Improvements to ICHS Layout Roads in Ward No. 09, Vidyaranyapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of B B UMESHA	
				In Figures	In Words
1	370.58	Earth work excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	110.0	Rupees One Hundred Ten Only
2	445.5	Removing B.S. Slab Drain and stacking etc complete as per specifications and directions of engineer in charge of the work	Sqm	65.0	Rupees Sixty Five Only
3	445.5	Refixing stone slabs of drains and pointing in CM (1:3) etc complete as per specifications and directions of engineer in charge of the work	Sqm	80.0	Rupees Eighty Only
4	243.45	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density etc complete as per specifications and directions of engineer in charge of the work	Cum	1500.0	Rupees One Thousand Five Hundred Only
5	2227.5	Cleaning the existing WBM road surface including removing of binding materials and other foreign matter with wire bushes and small picks, sweeping with brooms or soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	14.0	Rupees Fourteen Only
6	2227.5	Providing and applying primer coat for surfaces of medium porosity like cement stabilized soil base @ 1.10 Kg/sqmt over prepared surface with S.S bitumen emulsion using bitumen tanker fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	Sqm	80.0	Rupees Eighty Only
7	55.69	Providing and laying semi dense bituminous concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 508 complete in all respects as per specifications. using 100-120 TPH capacity H.M.P with sensor paver grading II (25-30mm) with 5% CRMB-55 grade etc complete as per specifications and directions of engineer in charge of the work	Cum	11500.0	Rupees Eleven Thousand Five Hundred Only

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

8	370.58	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inlcuding loading and unloading etc complete as per specifications and directions of engineer in charge of the work	Cum	74.0	Rupees Seventy Four Only

Signature of the Contractor

Executive Engineer
Byaravanapura Division
BBMP, Bangalore- 92